

A STREET REVITALIZATION
MAIN STREET TO CERVANTES STREET
PHASE I - GARDEN STREET TO CERVANTES STREET

Bid Tab - Final Submittal

1/27/2022

	ITEM #	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
ROADWAY						
1	0101-1	MOBILIZATION (INCLUDES NPDES PERMITTING)	1	LS		
2	0102-1	MAINTENANCE OF TRAFFIC	1	LS		
3	0104-1	EROSION CONTROL	1	LS		
4	0110-1-1	CLEARING AND GRUBBING (INCLUDES SAW CUTTING/MISCELLANEOUS ASPHALT REMOVAL)	1	LS		
5	NON-FDOT	EARTHWORK (MINOR REGRADING/SHAPING/FILL/EXCAVATION)	1	LS		
6	0110-4-10	REMOVAL OF EXISTING CONCRETE PAVEMENT	4599	SY		
7	0327-70-6	MILLING EXISTING ASPHALT PAVEMENT (1-1/2" AVG DEPTH)	2416	SY		
8	0337-7-81	ASPHALT CONCRETE FRICTION COURSE (TRAFFIC B)(FC 12.5)(PG 76-22)	200	TN		
9	NON-FDOT	12" CONCRETE RIBBON CURB (6" THICK) (F&I) (3000 PSI)	694	LF		
10	0520-2-4	CONCRETE CURB, TYPE D	18	LF		
11	0522-1	CONCRETE SIDEWALK, 4" THICK	4792	SY		
12	0522-2	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	1426	SY		
13	0527-2	DETECTABLE WARNINGS	910	SF		
14	NON-FDOT	60 MM CONCRETE PAVER SIDEWALK EDGE SOLDIER COURSE (2 SIDES AND DETAILS)	10671	LF		
15	NON-FDOT	COMPASS ROSE EMBOSSEING TEMPLATE & PERPENDICULAR BRICK (10% SURPLUS TEMPLATES) (F&I)	67	EA		
16	NON-FDOT	CAST IRON STREET NAME EMBEDDED IN SIDEWALK (INSTALL ONLY)	32	EA		
17	NON-FDOT	ISLANDS - (INCLUDES SAWCUTTING, REMOVAL OF ASPHALT AND BASE, EXCAVATION UP TO 2', FDOT TYPE D CURB	27	EA		

A STREET REVITALIZATION
MAIN STREET TO CERVANTES STREET
PHASE I - GARDEN STREET TO CERVANTES STREET

Bid Tab - Final Submittal

1/27/2022

	ITEM #	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
SIGNING AND PAVEMENT MARKINGS						
1	0700 1 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	12	AS		
2	0700 1 50	SINGLE POST SIGN, RELOCATE	24	AS		
3	0706 1 3	RAISED PAVEMENT MARKER, TYPE B	331	EA		
4	*	REFLECTIVE PAVEMENT MARKER (RPM) (YELLOW/ YELLOW)	311	EA		
5	*	REFLECTIVE PAVEMENT MARKER (RPM) (WHITE / RED)	20	EA		
6	0711 11123	THERMOPLASTIC, STANDARD, WHITE, SOLID 12" FOR CROSSWALK	2257	LF		
7	0711 11125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	2764	LF		
8	0711 11170	THERMOPLASTIC, STANDARD, WHITE, ARROW (LEFT)	8	EA		
9	0711 11224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	180.5	LF		
10	0711 14160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE OR SYMBOL (BICYCLE WITH CHEVRON) (WHEELCHAIR/UNIVERSAL SYMBOL OF ACCESSIBILITY)	30	EA		
11	0711 16101	THERMOPLASTIC, STANDARD - OTHER SURFACES, WHITE SOLID, 6"	0.61	GM		
12	0711 16201	THERMOPLASTIC, STANDARD - OTHER SURFACES, YELLOW, SOLID, 6"	1.18	GM		
13	NON- FDOT	CONFLICTING PAVEMENT MARKING REMOVAL (HYDROBLASTING)	1	LS		

A STREET REVITALIZATION
MAIN STREET TO CERVANTES STREET
PHASE I - GARDEN STREET TO CERVANTES STREET

Bid Tab - Final Submittal

1/27/2022

ITEM #	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
LANDSCAPE					
1	EAST PALATKA HOLLY	5	45 GAL		
2	NATCHEZ CRAPE MYRTLE	69	100 GAL		
3	LITTLE GEM MAGNOLIA	3	30 GAL		
4	LIVE OAK	1	65 GAL		
5	SUNSHINE LIGUSTRUM	821	3 GAL		
6	ASIAN JASMINE	10993	1 GAL		
7	SOD	1435	SY		
8	SOIL	687	CY		
9	PINESTRAW MULCH	5563	SY		
10	TREE REMOVAL	36	EA		
IRRIGATION COMPLETE					
1	IRRIGATION	1	LS		
LIGHTING					
1	Light Poles and Concrete Base	70	EA		
2	New Panel Board w/ Breakers	1	EA		
3	New Surge Suppressor	1	EA		
4	New Contactor	2	EA		
5	Panel Board Enclosure	1	EA		
6	Directional Bore Mobilization	1	EA		

A STREET REVITALIZATION
MAIN STREET TO CERVANTES STREET
PHASE I - GARDEN STREET TO CERVANTES STREET

Bid Tab - Final Submittal

1/27/2022

	ITEM #	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
	7	Directional Bore	850	LF		
	8	Trench	5400	LF		
	9	#6 Wire	450	CLF		
	10	2" PVC	6250	LF		
TOTAL						